

Custom Procurement Report

Control How You Source Building Systems

Directly access suppliers and automate sourcing, procurement, and financing—all from one platform



Customer Information

Customer Town of Montgomery Police Station

Name Contact Matt Seckler

Person Contact mseckle

Email mseckler@consigli.com

Contact 845-391-1925

Phone Bid Due 05/23/2025 02:00 PM

Date Construction Consigli Construction Co., Inc.

Manager
Architect ADG Architects (Jason T. Anderson Architect, P.C.)

Engineer Of M/E Engineering (Schenectady, NY)

Project Information

Project Town of Montgomery Police Station HVAC System

Name

Location 110 Bracken Road, Montgomery, NY 12549

Start Date 02-24-25

 $\begin{array}{ll} \textbf{Completion} & \text{N/A} \\ \textbf{Date} & \text{Budget} & \text{N/A} \\ \end{array}$

Scope HVAC and Plumbing Systems Installation

Project ID TOM Police Station
Project URL BuildVision Project Link

Design Bid Documents

Stage
Project StaRidding

tus
Applicable
Bidding

Specifica- 22 0000 - Plumbing, 23 0000 - HVAC, 26 0000 - Electrical

tions

Prepared By

Ben Lyddane Ben@BuildVision.io 202-365-8628

Mackenzie Hoover Mackenzie@buildvision.io 843-609-3265

Date: 2025-05-20

Project Equipment

Packaged Rooftop Air Handling Units

Equipment Tag	Manufacturer	Model
RTU-1	Daikin Applied	DPSH03B
RTU-2	Daikin Applied	DPSH12B

Notes

DX/Electric heat pump units with economizer capability; 10-20 week lead time

Split System Air Conditioning Units

Equipment Tag	Manufacturer	Model
AC-01	Trane	MSZ-GS36NA (Indoor) / MUZ-GS36NA (Outdoor)

Notes

Heat Pump Type; 10-20 week lead time

Exhaust Fans

Equipment Tag	Manufacturer	Model
EF-1	Greenheck	G-120-VG
EF-122	Greenheck	G-060-VG
EF-124	Greenheck	G-060-VG

Notes

Downblast type for roof installation; 10-14 week lead time

Unit Heaters

Equipment Tag	Manufacturer	Model
UH-111	QMark	MUH0581-PRO
UH-125	QMark	MUH0581-PRO

Notes

Electric unit heaters; <10 week lead time

Cabinet Unit Heaters

Equipment Tag	Manufacturer	Model
CUH-1	QMark	AWH4408
CUH-2	QMark	EFF4008

Notes

Electric cabinet heaters; <10 week lead time

Plumbing Fixtures

Equipment Tag	Manufacturer	Model
DF-1	Elkay Manufacturing Company	LZWSM8K
DF-2	Elkay Manufacturing Company	LZS-LRPBM28K
MS-1	Fiat	TSB-300

Notes

As specified in Section 22 40 00

Water Treatment Equipment

Equipment Tag	Manufacturer	Model
SF-1	Watts	PHSJUM40
UV-A	VIQUA	PRO20
UV-B	VIQUA	PRO20

Notes

As specified in Section 22 67 00

Equipment Curbs and Supports

Equipment Tag	Manufacturer	Model
EC-1	RPS	Custom
PC-1	RPS	Custom

Notes

Wind-rated supports for rooftop equipment; <10 week lead time

Suppliers

Packaged Rooftop Air Handling Units

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
Daikin	Applied DPSH Series	N/A		Basis of Design	Yes
Carrier	48HC	RJ Murray Company	+3-5%	Compatible with specified requirements. 208V/3-Phase electrical connection.	No
Trane	Precedent	Trane Tech- nologies	+2-4%	Compatible with specified requirements. 208V/3-Phase electrical connection.	No
York	Predator	Johnson Controls	+1-3%	Compatible with specified requirements. 208V/3-Phase electrical connection.	No

Split System Air Conditioning Units

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
Trane	MSZ- GS36NA/MUZ GS36NA	N/A		Basis of Design	Yes

Ultraviolet Sterilizers

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
VIQUA	PRO20	N/A		Basis of Design	Yes

Atlantic Ultraviolet	Sanitron S5000C	Atlantic Ul- traviolet Corporation	-2-5%	Must meet NSF Standard 61 and Standard 55 Class A certification as required by NYS Department of Health.	No
Trojan Tech- nologies	UV Max Pro20	Trojan Tech- nologies	+3-7%	Must meet NSF Standard 61 and Standard 55 Class A certification as required by NYS Department of Health.	No

Exhaust Fans

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
Greenheck	G-Series	N/A		Basis of Design	Yes
Loren Cook	ACE-B	RF Peck Company, Inc.	-1-3%	Compatible with specified requirements.	No
PennBarry	Domex	Kane-Davey Associates, Inc.	-2-4%	Compatible with specified requirements.	No

Unit Heaters & Cabinet Unit Heaters

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
QMark	MUH Se- ries/AWH Series	N/A		Basis of Design	Yes
Markel	HF/HT Series	Applied Thermal Systems Inc.	-3-5%	Compatible with specified requirements. Verify panel compatibility.	No
Berko	HUHAA Series	Electrical Equipment Corp.	+1-4%	Compatible with specified requirements. Verify panel compatibility.	No

Equipment Curbs and Supports

Note: Cost differences are Al-estimated percentages relative to Basis of Design and are not based on actual project data. Always obtain accurate quotes from vendors directly via buildvision.io.

Manufacturer	Model	Representativ	Al Est. Cost D	Compatibility Notes	BoD
RPS	Custom	N/A		Basis of Design	Yes

Design Notes

Rooftop HVAC Systems

Technical Observations:

- System designed with packaged rooftop heat pump units with economizer capability for fresh air intake
- Variable air volume distribution system for improved energy efficiency
- Minimum of VAV boxes with electric reheat for zone control
- Exhaust systems designed for proper building ventilation
- Long-lead risk on Daikin RTUs with 10-20 week lead times
- Wind restraint requirements for all rooftop equipment per Division 23

Concerns:

- Ensuring proper weatherproofing at all roof penetrations
- · Maintaining adequate access for maintenance of rooftop equipment
- · Sizing of ductwork for proper air distribution with minimal noise
- Lead time risk for critical equipment could impact project schedule
- Ductless Split model naming (MSZ/MUZ) shows Mitsubishi designations while specified as Trane

Opportunities:

- High-efficiency heat pump systems for reduced energy consumption
- Demand controlled ventilation opportunities where applicable
- Economizer operation during moderate weather conditions
- · Early procurement of long-lead items to mitigate schedule risk

Water Treatment Systems

Technical Observations:

- · Sediment filtration system with 20 micron filter for incoming water
- Dual UV disinfection system with redundancy in case of failure
- NSF Standard 61 and Standard 55 Class A certification as required by NYS Department of Health

Concerns:

- Ensuring proper installation of UV systems with adequate clearance for lamp replacement
- Providing robust water quality monitoring and backup systems
- · Maintaining proper flow rates through treatment equipment

Opportunities:

- Parallel installation of UV systems allows for maintenance without system shutdown
- System designed for 40 GPM total capacity (2 x 20 GPM units)

Plumbing Systems

Technical Observations:

- ADA-compliant fixtures throughout
- · High-efficiency water coolers with bottle filling stations
- Specialized service basin fixtures in janitorial areas

Concerns:

- Ensuring proper installation of backflow prevention devices
- Coordinating fixture rough-ins with architectural details

Opportunities:

- Water-efficient fixtures to reduce overall consumption
- Durable materials selection for long service life

BuildVision Recommendations

1. Install additional monitoring systems for water treatment equipment

Rationale: The current design includes dual UV disinfection systems but would benefit from real-time monitoring to ensure continuous operation and immediate notification of any issues.

Estimated Impact: Increased reliability of water treatment system and reduced risk of water quality issues.

Implementation: Add water quality monitoring system with remote notification capabilities to alert maintenance staff of any issues.

Priority: High

2. Implement advanced controls for rooftop units

Rationale: The specified HVAC equipment supports advanced controls that could optimize performance beyond the base requirements.

Estimated Impact: Potential energy savings of 10-15% through optimized operation and enhanced economizer control.

Implementation: Upgrade control sequences to include demand-controlled ventilation and integration with building automation system.

Priority: Medium

3. Provide additional roof curb insulation

Rationale: Standard roof curbs may create thermal bridging that can reduce overall system efficiency.

Estimated Impact: Reduction in energy loss and potential condensation issues.

Implementation: Specify higher R-value insulation for rooftop equipment curbs beyond

minimum requirements.

Priority: Medium

4. Implement comprehensive commissioning plan

Rationale: Complex HVAC and water treatment systems require thorough commissioning to ensure proper operation.

Estimated Impact: Verification of proper system operation and documentation for future maintenance.

Implementation: Develop detailed commissioning plan including testing of all control sequences and system performance metrics.

Priority: High

5. Schedule early procurement of long-lead equipment

Rationale: Daikin RTUs have 10-20 week lead times which could impact project schedule if not ordered early.

Estimated Impact: Avoidance of potential project delays of 4-8 weeks.

Implementation: Early submittal and procurement process for Daikin RTUs and other long-

lead items. **Priority:** High

6. Verify ductless split system model compatibility

Rationale: Trane split system specifications show model numbers with Mitsubishi designa-

tions (MSZ/MUZ), indicating potential supply chain or specification issue. **Estimated Impact:** Prevention of procurement delays and installation issues.

Implementation: Coordinate with design team to verify correct manufacturer and model

specifications before procurement.

Priority: High

7. Ensure wind restraint submittals meet requirements

Rationale: Division 23 requires PE-stamped calculations and submittals for rooftop equipment curbs and supports.

Estimated Impact: Compliance with code requirements and prevention of inspection issues.

Implementation: Coordinate with structural engineer for wind restraint design and certifi-

cation of all rooftop equipment. **Priority:** Medium

Conclusion

Key Findings

- The selected equipment meets or exceeds energy efficiency requirements
- The HVAC system provides appropriate zoning for different building areas
- Water treatment systems include redundancy for critical functions
- The overall design follows current best practices for safety and reliability
- Long lead times for Daikin RTUs (10-20 weeks) present schedule risk
- Model number discrepancies in the ductless split system specifications need resolution
- Wind restraint requirements for rooftop equipment require PE certification

Highest Priority Actions

- Implement comprehensive commissioning plan to verify proper system operation
- Schedule early procurement of long-lead equipment to prevent schedule delays
- Install additional monitoring for water treatment systems
- Verify ductless split system model compatibility before procurement
- Ensure PE-stamped wind restraint submittals for all rooftop equipment
- Provide detailed training for maintenance staff on all specialized equipment

Summary

The HVAC and plumbing systems designed for the Town of Montgomery Police Station incorporate energy-efficient equipment and provide for reliable operation. The use of variable air volume distribution with heat pump technology balances energy efficiency with occupant comfort. The water treatment system meets regulatory requirements while providing redundancy for critical functions. Several issues require attention, including long lead times for critical equipment, model number discrepancies for the ductless split system, and wind restraint requirements for rooftop equipment.



Ben Lyddane Ben@BuildVision.io 202-365-8628

Mackenzie Hoover Mackenzie@buildvision.io 843-609-3265

Date: 2025-05-20