

# Custom Procurement Report

# **Control How You Source Building Systems**

Directly access suppliers and automate sourcing, procurement, and financing—all from one platform



## **Customer Information**

**Customer Name** Town of Montgomery Police Station

Contact Person Matt Seckler

Contact Email mseckler@consigli.com

**Contact Phone** 845-391-1925

**BidDueDate** 05/23/2025 02:00 PM

ConstructionManager Consigli Construction Co., Inc.

Architect ADG Architects (Jason T. Anderson Architect, P.C.)

**EngineerOfRecord** M/E Engineering (Schenectady, NY)

# **Project Information**

Project Name Town of Montgomery Police Station HVAC System

**Location** 110 Bracken Road, Montgomery, NY 12549

**Start Date** 02-24-25

**Completion Date** N/A **Budget** N/A

**Scope** HVAC and Plumbing Systems Installation

Project ID TOM Police Station
Project URL BuildVision Project Link

**DesignStage** Bid Documents

ProjectStatus Bidding

ApplicableSpecification\$2 0000 - Plumbing, 23 0000 - HVAC, 26 0000 - Electrical

# **Prepared By**

Ben Lyddane

Ben@BuildVision.io

202-365-8628

Mackenzie Hoover

Mackenzie@buildvision.io

843-609-3265

Date: 05-14-25

# **Project Equipment**

# **Packaged Rooftop Air Handling Units**

<b>Equipment Tag</b>	Manufacturer	Model
RTU-1	Daikin Applied	DPSH03B
RTU-2	Daikin Applied	DPSH12B

### Notes

DX/Electric heat pump units with economizer capability; 10-20 week lead time

# **Split System Air Conditioning Units**

<b>Equipment Tag</b>	Manufacturer	Model
AC-01	Trane	MSZ-GS36NA (Indoor) / MUZ-GS36NA (Outdoor)

### Notes

Heat Pump Type; 10-20 week lead time

### **Exhaust Fans**

<b>Equipment Tag</b>	Manufacturer	Model
EF-1	Greenheck	G-120-VG
EF-122	Greenheck	G-060-VG
EF-124	Greenheck	G-060-VG

### **Notes**

Downblast type for roof installation; 10-14 week lead time

# **Unit Heaters**

<b>Equipment Tag</b>	Manufacturer	Model
UH-111	QMark	MUH0581-PRO
UH-125	QMark	MUH0581-PRO

#### Notes

Electric unit heaters; <10 week lead time

### **Cabinet Unit Heaters**

<b>Equipment Tag</b>	Manufacturer	Model
CUH-1	QMark	AWH4408
CUH-2	QMark	EFF4008

#### Notes

Electric cabinet heaters; <10 week lead time

# **Plumbing Fixtures**

<b>Equipment Tag</b>	Manufacturer	Model
DF-1	Elkay Manufacturing Company	LZWSM8K
DF-2	Elkay Manufacturing Company	LZS-LRPBM28K
MS-1	Fiat	TSB-300

### **Notes**

As specified in Section 22 40 00

# **Water Treatment Equipment**

<b>Equipment Tag</b>	Manufacturer	Model
SF-1	Watts	PHSJUM40
UV-A	VIQUA	PRO20
UV-B	VIQUA	PRO20

### Notes

As specified in Section 22 67 00

# **Equipment Curbs and Supports**

<b>Equipment Tag</b>	Manufacturer	Model
EC-1	RPS	Custom
PC-1	RPS	Custom

#### Notes

Wind-rated supports for rooftop equipment; <10 week lead time

# **Suppliers**

# **Packaged Rooftop Air Handling Units**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
Daikin	Applied DPSH Series	N/A	Basis of Design	Yes
Daikin Ap- plied	DPSH Series	Thermal Environment Sales	Basis of Design unit.	No
Carrier	48HC	RJ Murray Company	Compatible with specified requirements. 208V/3-Phase electrical connection.	No
Trane	Precedent	Trane Tech- nologies	Compatible with specified requirements. 208V/3-Phase electrical connection.	No
York	Predator	Johnson Controls	Compatible with specified requirements. 208V/3-Phase electrical connection.	No

# **Split System Air Conditioning Units**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
Trane	MSZ- GS36NA/MUZ GS36NA	N/A	Basis of Design	Yes
Trane	MSZ- GS36NA/MUZ GS36NA	Trane Tech- -nologies	Basis of Design unit. Note: Model naming uses Mitsubishi designation; verify compatibility.	No

# **Ultraviolet Sterilizers**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
VIQUA	PRO20	N/A	Basis of Design	Yes
VIQUA	PRO20	VIQUA (Tro- jan Technolo- gies)	,	No
Atlantic Ultraviolet	Sanitron S5000C	Atlantic UI- traviolet Corporation	Must meet NSF Standard 61 and Standard 55 Class A certification as required by NYS Department of Health.	No

Trojan Tech-	UV Max	Trojan Tech-	Must meet NSF Standard 61 and Stan-	No
nologies	Pro20	nologies	dard 55 Class A certification as required	
-			by NYS Department of Health.	

# **Exhaust Fans**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
Greenheck	G-Series	N/A	Basis of Design	Yes
Greenheck	G-Series	Buckley Associates	Basis of Design unit.	No
Loren Cook	ACE-B	RF Peck Company, Inc.	Compatible with specified requirements.	No
PennBarry	Domex	Kane-Davey Associates, Inc.	Compatible with specified requirements.	No

# **Unit Heaters & Cabinet Unit Heaters**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
QMark	MUH Se- ries/AWH Series	N/A	Basis of Design	Yes
QMark	MUH Se- ries/AWH Series	QMark (Mar- ley Engi- neered Products)	Basis of Design unit.	No
Markel	HF/HT Series	Applied Thermal Systems Inc.		No
Berko	HUHAA Series	Electrical Equipment Corp.	Compatible with specified requirements. Verify panel compatibility.	No

# **Equipment Curbs and Supports**

Manufacturer	Model	Representativ	Compatibility Notes	BoD
RPS	Custom	N/A	Basis of Design	Yes
RPS	Custom	Roof Products & Systems Corporation	Basis of Design custom equipment curbs with wind-rated design.	No

# **Design Notes**

## **Rooftop HVAC Systems**

#### **Technical Observations:**

- System designed with packaged rooftop heat pump units with economizer capability for fresh air intake
- Variable air volume distribution system for improved energy efficiency
- · Minimum of VAV boxes with electric reheat for zone control
- Exhaust systems designed for proper building ventilation
- Long-lead risk on Daikin RTUs with 10-20 week lead times
- Wind restraint requirements for all rooftop equipment per Division 23

#### **Concerns:**

- Ensuring proper weatherproofing at all roof penetrations
- · Maintaining adequate access for maintenance of rooftop equipment
- · Sizing of ductwork for proper air distribution with minimal noise
- Lead time risk for critical equipment could impact project schedule
- Ductless Split model naming (MSZ/MUZ) shows Mitsubishi designations while specified as Trane

#### **Opportunities:**

- High-efficiency heat pump systems for reduced energy consumption
- Demand controlled ventilation opportunities where applicable
- Economizer operation during moderate weather conditions
- · Early procurement of long-lead items to mitigate schedule risk

### **Water Treatment Systems**

#### **Technical Observations:**

- Sediment filtration system with 20 micron filter for incoming water
- Dual UV disinfection system with redundancy in case of failure
- NSF Standard 61 and Standard 55 Class A certification as required by NYS Department of Health

#### Concerns:

- Ensuring proper installation of UV systems with adequate clearance for lamp replacement
- Providing robust water quality monitoring and backup systems
- · Maintaining proper flow rates through treatment equipment

#### **Opportunities:**

- Parallel installation of UV systems allows for maintenance without system shutdown
- System designed for 40 GPM total capacity (2 x 20 GPM units)

## **Plumbing Systems**

#### **Technical Observations:**

- ADA-compliant fixtures throughout
- · High-efficiency water coolers with bottle filling stations
- Specialized service basin fixtures in janitorial areas

#### **Concerns:**

- Ensuring proper installation of backflow prevention devices
- Coordinating fixture rough-ins with architectural details

#### **Opportunities:**

- Water-efficient fixtures to reduce overall consumption
- Durable materials selection for long service life

### **BuildVision Recommendations**

### 1. Install additional monitoring systems for water treatment equipment

**Rationale:** The current design includes dual UV disinfection systems but would benefit from real-time monitoring to ensure continuous operation and immediate notification of any issues.

**Estimated Impact:** Increased reliability of water treatment system and reduced risk of water quality issues.

**Implementation:** Add water quality monitoring system with remote notification capabilities to alert maintenance staff of any issues.

**Priority:** High

# 2. Implement advanced controls for rooftop units

**Rationale:** The specified HVAC equipment supports advanced controls that could optimize performance beyond the base requirements.

**Estimated Impact:** Potential energy savings of 10-15% through optimized operation and enhanced economizer control.

**Implementation:** Upgrade control sequences to include demand-controlled ventilation and integration with building automation system.

**Priority:** Medium

#### 3. Provide additional roof curb insulation

**Rationale:** Standard roof curbs may create thermal bridging that can reduce overall system efficiency.

**Estimated Impact:** Reduction in energy loss and potential condensation issues.

Implementation: Specify higher R-value insulation for rooftop equipment curbs beyond

minimum requirements.

**Priority: Medium** 

## 4. Implement comprehensive commissioning plan

**Rationale:** Complex HVAC and water treatment systems require thorough commissioning to ensure proper operation.

**Estimated Impact:** Verification of proper system operation and documentation for future maintenance.

**Implementation:** Develop detailed commissioning plan including testing of all control sequences and system performance metrics.

**Priority:** High

## 5. Schedule early procurement of long-lead equipment

**Rationale:** Daikin RTUs have 10-20 week lead times which could impact project schedule if not ordered early.

**Estimated Impact:** Avoidance of potential project delays of 4-8 weeks.

Implementation: Early submittal and procurement process for Daikin RTUs and other long-

lead items. **Priority:** High

## 6. Verify ductless split system model compatibility

**Rationale:** Trane split system specifications show model numbers with Mitsubishi designations (MSZ/MUZ), indicating potential supply chain or specification issue.

**Estimated Impact:** Prevention of procurement delays and installation issues.

Implementation: Coordinate with design team to verify correct manufacturer and model

specifications before procurement.

**Priority:** High

### 7. Ensure wind restraint submittals meet requirements

**Rationale:** Division 23 requires PE-stamped calculations and submittals for rooftop equipment curbs and supports.

**Estimated Impact:** Compliance with code requirements and prevention of inspection issues.

Implementation: Coordinate with structural engineer for wind restraint design and certifi-

cation of all rooftop equipment. **Priority:** Medium

### Conclusion

## **Key Findings**

- The selected equipment meets or exceeds energy efficiency requirements
- The HVAC system provides appropriate zoning for different building areas
- Water treatment systems include redundancy for critical functions
- The overall design follows current best practices for safety and reliability
- Long lead times for Daikin RTUs (10-20 weeks) present schedule risk
- Model number discrepancies in the ductless split system specifications need resolution
- Wind restraint requirements for rooftop equipment require PE certification

## **Highest Priority Actions**

- Implement comprehensive commissioning plan to verify proper system operation
- Schedule early procurement of long-lead equipment to prevent schedule delays
- Install additional monitoring for water treatment systems
- Verify ductless split system model compatibility before procurement
- Ensure PE-stamped wind restraint submittals for all rooftop equipment
- Provide detailed training for maintenance staff on all specialized equipment

#### **Summary**

The HVAC and plumbing systems designed for the Town of Montgomery Police Station incorporate energy-efficient equipment and provide for reliable operation. The use of variable air volume distribution with heat pump technology balances energy efficiency with occupant comfort. The water treatment system meets regulatory requirements while providing redundancy for critical functions. Several issues require attention, including long lead times for critical equipment, model number discrepancies for the ductless split system, and wind restraint requirements for rooftop equipment.



Ben Lyddane Ben@BuildVision.io 202-365-8628

Mackenzie Hoover Mackenzie@buildvision.io 843-609-3265

Date: 05-14-25